GEO SURFACES

A Professional Engineering Firm

PROPOSAL FOR GEOGREEN™ GEOFLO™ INSTALLATION

Project Name: City of Euless, Attn: Ray McDonald, 201 N. Ector, Euless, TX 76039
Phone: 817.685.1669 Email: rmcdonald@eulesstx.gov

Global Synthetics Environmental, LLC, an authorized TIPS Vendor (herein called ***Geo-Surfaces***) will provide all materials, labor and equipment necessary to install a ***GeoGreen™*** infilled 'replicated grass' fields with a sand colored radius infield with a 5' green halo on a ***GeoFlo™*** drainage and shock attenuation blanket for the City of Euless, TX (actual field dimensions, turf panel configuration and resulting square footage of purchase and/or amount of material shipped, to be determined). ***Geo-Surfaces*** will install the replicated grass and drainage blanket on a base and perimeter anchor constructed by ***GeoSurfaces*** consistent with the requirements in the attached ***GeoGreen™/GeoFlo™ Installation Guide Specifications*** that is made part of this Proposal by reference. The field will be solid green with a sand colored infield and home plate circle, permanently inlaid white foul lines, coach's boxes and batters boxes. The field will have color layouts and base pegs located per the attached drawing. One portable artificial mound is included in this proposal. One constructed concrete mound covered with artificial turf is included in this proposal. The TIPS Cooperative Fee is included in this proposal.

The physical performance criteria and replicated grass specifications are as stated in the ***GeoGreen™/GeoFlo™ Installation Guide Specifications*** referenced above. The warranty provided by ***Geo-Surfaces*** is the attached ***Geo-Surfaces Warranty***. The **Contract Agreement** under which ***Geo-Surfaces*** will perform the Scope of Work is attached and made a part hereof by reference.

Commencement of work and shipment of materials shall be in conformance with project specifications and completion of installation shall be per the project schedule agreed to by the parties. Installation will commence following the availability and access to the site by ***Geo-Surfaces*** before November 15, 2016. Installation is estimated to be completed in approximately 65 good weather working days. Production of the materials must begin by October 31, 2016 or the terms of this offer will be renegotiated.

TOTAL COST for materials, labor & equipment to be provided by ***Geo-Surfaces for field installations*** **$1,116,950.00**

Geo-Surfaces will deduct $110,000.00 from the proposed price for a Marketing and Brand Awareness (MBA) Agreement that would include logos on the fields included on this complex as well as the new LEGENDS field constructed under separate contract. The MBA will include marketing that includes "Geo-Surfaces Fields at the Parks at Texas Star" as well as the "official surface of the Parks at Texas Star".

TAXES: __ Included X Excluded (see **Terms** below)

TERMS:

- The cost of permits, city engineering fees, water management fees or other license fees, if applicable, will be provided by others.
- Surveying for field placement will be provided by Geo-Surfaces.
- Installation must commence on or before November 15, 2016 or the terms of the Contract will be renegotiated.
- Installation shall not be interrupted or delayed by Purchaser for any reason without prior written approval from Geo-Surfaces.
- Installation will commence within 15 days of Purchaser's written notice. Completion will be within the agreed upon good weather working days. "Good weather working days" are defined in the Contract Agreement.
- Taxes will be excluded to Purchaser in accordance with the laws of the state of the project. Purchaser must provide Geo-Surfaces with a valid tax exemption. Purchaser agrees that if the exemption provided is deemed invalid by the applicable state tax authorities, Purchaser will reimburse Geo-Surfaces for taxes Geo-Surfaces was required to remit.
- A certificate of insurance will be issued to Purchaser upon mobilization to the project site.
- The TIPS Cooperative Fee is included in this proposal.
- Core testing, density testing or geotechnical testing is not included as part of this proposal.

Acceptance of Offer to Sell: This offer to sell (Proposal and all attachments) is valid for acceptance by Purchaser by the execution of the Acceptance of Proposal below and return of an original to Geo-Surfaces. If the Acceptance of Proposal is not received by Geo-Surfaces on or before the Proposal expiration date, this offer to sell shall be deemed automatically cancelled and withdrawn.

Proposal tendered this 27th day of September 2016. Proposal expires the 31st day of October 2016.

For: **GEO-SURFACES**

By:_____

ACCEPTANCE OF PROPOSAL

By your signature below and the return of an originally executed Acceptance of Proposal within the time specified for acceptance of Geo-Surfaces' offer to sell, you accept the terms and conditions contained in the Proposal; the Contract Agreement; the GeoGreen and GeoFlo Installation Guide Specifications; the Geo-Surfaces Warranty; the Maintenance Requirement Manual.

PURCHASER: _____

By: _____

(Name and Title)

Date: _____ Federal Tax ID # _____